#### **ABBREVIATIONS**

48" ABOVE FINISHED FLOOR A/AMP AMPERE ALTERNATING CURRENT ABOVE FINISHED FLOOR AFF AFG ABOVE FINISHED GRADE AMPS INTERRUPTING CURRENT APPROX APPROXIMATE AUTOMATIC TEMPERATURE CONTROL ATC AMERICAN WIRE GAUGE

AWG CONDUIT C/B CIRCUIT BREAKER CKT CIRCUIT CLG CEILING DC DIRECT CURRENT DEG or \* DEGREE DIAMETER DIA or Ø DN DOWN DWG DRAWING

EFF **EFFICIENCY** EHC **ELECTRICAL HEATING CABLES ELEC** ELECTRICAL

**ELEV** ELEVATOR EM **EMERGENCY** EMT ELECTRIC METALLIC TUBING **FAHRENHEIT** FΑ FIRE ALARM FC FOOT CANDLE FOOT OR FEET GROUND FAULT GND GROUND

HEIGHT

HORSEPOWER HOUR(S) FREQUENCY (CYC, PER SEC.) INCHES

ΗZ JUNCTION BOX KVA KILOVOLT AMPERE KW KILOWATT LENGTH LINEAR FEET MILLIAMPERE MC METAL CLAD CABLE MECH MECHANICAL MFR **MANUFACTURER** METAL HALIDE MLO MAIN LUGS ONLY N/A NOT APPLICABLE N.C. NORMALLY CLOSED

NEC NATIONAL ELECTRICAL CODE NIC N.O. NOT IN CONTRACT NORMALLY OPEN NTS NOT TO SCALE POWER FACTOR

PH / ø PHASE PVC POLYVINYL CHLORIDE RD ROOF DRAIN RGS RIGID GALVANIZED STEEL CONDUIT RMROOM RWL

RAIN WATER LEADER SE SECONDARY ELECTRIC SERVICE SPDT SINGLE POLE DOUBLE THROW SPEC SPECIFICATION SPST SINGLE POLE SINGLE THROW SQUARE

SQ SWBD SWITCHBOARD

TRANSFORMER

IDENTIFICATION OF EQUIPMENT TELECOMMUNICATIONS SERVICE TAMPERPROOF

TYPICAL VOLTAGE **VOLT AMPERE** VA VERIFY IN FIELD WATT WG WIREGUARD WEATHERPROOF

TEL

## **ELECTRICAL SYMBOLS** LINEAR LIGHT FIXTURE

0 SURFACE-MOUNTED FIXTURE SINGLE-POLE SWITCH TIME CLOCK

 $\square_{PC}$ PHOTOCELL ₩. DUPLEX RECEPTACLE RACEWAY UP/DOWN

0

**—**0 0 POWER WIRING SWITCH LEG WIRING \_\_\_\_ CONTROL WIRING CIRCUIT BREAKER SIZE

XXÁ-XP HOME RUN XX-X PANEL DESIGNATION SURFACE ELECTRICAL PANEL, 480Y/277 OR 480 VOLT

> SURFACE ELECTRICAL PANEL, 208Y/120 OR 208 VOLT SURFACE SPECIAL-PURPOSE PANEL OR CABINET

TRANSFORMER ENCLOSED CONTROLLER **ENCLOSED SWITCH** 

ELECTRIC MOTOR J JUNCTION BOX TB TERMINAL BOX RELAY IN ENCLOSURE

С CONTACTOR IN ENCLOSURE SUBLETTERS "EX" INDICATES EXISTING EX EQUIPMENT TO REMAIN INTACT SUBLETTERS "RE" INDICATES EXISTING

> EQUIPMENT TO BE DISCONNECTED AND REMOVED \* = a, b, clg, AF, GF, IG OR TP. WHEN TAGGED ABOVE IN THE ELECTRICAL SYMBOL

# LIST, REFER TO THE ABBREVIATION LIST

# CODES LISTED BELOW APPLY TO ALL DRAWINGS AND SPECIFICATIONS ON THIS PROJECT

• 2003 INTERNATIONAL BUILDING CODE • 2005 SUPPLEMENT TO THE 2003 INTERNATIONAL BUILDING CODE

2011 AMENDMENT TO THE 2005 SUPPLEMENT TO THE 2003 INTERNATIONAL BUILDING CODE

 2005 CONNECTICUT STATE FIRE SAFETY CODE • 2009 AMENDMENT TO THE 2005 CONNECTICUT STATE FIRE SAFETY CODE

○ PART I — ADMINISTRATION

∘ PART II − GENERAL ○ PART III — NEW CONSTRUCTION, RENOVATIONS & CHANGE OF USE

• PART IV - EXISTING BUILDINGS/OCCUPANCIES

• PART V - MAINTENANCE AND OPERATIONAL ISSUES

• THE FOLLOWING AS REFERENCED BY THE ABOVE SUPPLEMENT, AMENDMENTS, AND CODES: 2003 INTERNATIONAL BUILDING CODE (IBC)

○ IEBC-03 INTERNATIONAL EXISTING BUILDING CODE 2003 INTERNATIONAL MECHANICAL CODE (IMC)

2003 INTERNATIONAL PLUMBING CODE (IPC)

2009 INTERNATIONAL ENERGY CONSERVATION CODE (IECC)

○ 2003 ICC/ANSI A117.1 - ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES ○ 2005 NFPA 70 - NATIONAL ELECTRICAL CODE (NEC)

2007 ANSI/ASHRAE/IESNA STANDARD 90.1 - ENERGY STANDARD FOR BUILDINGS EXCEPT LOW-RISE RESIDENTIAL

BUILDINGS ○ 1996 NFPA 54 — CONNECTICUT GAS FUEL CODE

○ 2002 NFPA 13 — INSTALLATION OF SPRINKLER SYSTEMS

• 2003 INTERNATIONAL ELECTRICAL CODE (ICC EC)

 2009 INTERNATIONAL FIRE CODE (IFC) ○ 2002 NFPA 72 - NATIONAL FIRE ALARM CODE

GUIDELINES (ADAAG) AND ADA REGULATIONS.

2002 NFPA 99 - STANDARD FOR HEALTH CARE FACILITIES

○ 2002 NFPA 110 - EMERGENCY AND STANDBY POWER SYSTEMS o 2003 ICC/ANSI A117.1 - GUIDELINES FOR ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES

• 1996 ASME A17.1 SAFETY CODE FOR ELEVATORS AND ESCALATORS WITH 1997 AND 1998 ADDENDAS

• 2002 CT PUBLIC HEALTH CODE • 2010 GUIDELINES FOR DESIGN AND CONSTRUCTION OF HEALTH CARE FACILITIES

• THE JOINT COMMISSION • THE AMERICANS WITH DISABILITIES ACT. TITLE II. INCLUDING THE AMERICANS WITH DISABILITIES ACT ACCESSIBILITY

• CONNECTICUT STATE DEPARTMENT OF EDUCATION (SDE), BUREAU OF SCHOOL FACILITIES (BSF) • GENERAL STATUTES OF CONNECTICUT WITH SUPPLEMENTS

• 2002 ASCE/SEI 7

#### **GENERAL NOTES**

#### GENERAL

- 1. THE PROJECT DRAWINGS AND SPECIFICATIONS ARE BASED ON THE CONSTRUCTION SPECIFICATIONS INSTITUTE (CSI) DOCUMENTATION FORMAT. SPECIFICATION AND DRAWING CONTENTS ARE ARRANGED BY TOPIC AND CATÉGORY AND ARE NOT INTENDED TO AWARD DIVISION OF WORK.
- 2. THE INTENT OF THESE DOCUMENTS IS FOR THE ELECTRICAL TRADES TO FURNISH AND INSTALL COMPLETE ELECTRICAL SYSTEMS. THE SPECIFIED ELECTRICAL AND SPECIAL SYSTEMS SHALL BE COMPLETE IN ALL RESPECTS: OPERATIONAL, TESTED, ADJUSTED, CALIBRATED, APPROVED BY THE AUTHORITIES HAVING JURISDICTION AND READY FOR BENEFICIAL USE BY THE OWNER.
- 3. THE TRADES SHALL OBTAIN AND REVIEW ALL CONTRACT DOCUMENTS BEFORE SUBMITTING A BID. INFORMATION IS PROVIDED ON THE VARIOUS DRAWINGS, SCHEDULES, SPECIFICATIONS AND ALL OF THE VARIOUS DOCUMENTS IN THE BIDDING PACKAGE. THE CONTRACT DOCUMENTS ARE COMPLEMENTARY AND FORM A TOTAL PROJECT DESIGN AND INFORMATION SOURCE FOR CONSTRUCTION PURPOSES.
- 4. THE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS AND WORK INCLUDED IN THE CONTRACT. COORDINATE LOCATIONS OF EQUIPMENT WITH OTHER TRADES BEFORE AND DURING CONSTRUCTION. ANY MODIFICATION TO THE EQUIPMENT LAYOUT, REQUIRED FOR INSTALLATION, IS TO BE PERFORMED UNDER THE CONTRACT AGREEMENT, AT NO ADDITIONAL COST.
- 5. REFER TO THE ARCHITECTURAL DRAWINGS FOR THE EXACT LOCATION AND MOUNTING HEIGHTS OF VARIOUS EQUIPMENT. ALL SUCH EQUIPMENT AND EQUIPMENT COLORS AND FINISHES SHALL BE COORDINATED WITH THE ARCHITECT; MOUNTING HEIGHTS SHALL BE APPROVED BY THE ARCHITECT.
- 6. PERFORM ALL WORK IN COMPLIANCE WITH THE SPECIFICATIONS APPLICABLE CODES, ORDINANCES AND THE REGULATORY AGENCIES HAVING JURISDICTION; THE SPECIFICATIONS MAY EXCEED THE REQUIREMENTS OF THE CODE: IN WHICH CASE, THE SPECIFICATION MUST BE FOLLOWED.
- 7. INSTALL ALL EQUIPMENT IN ACCESSIBLE LOCATIONS. WHERE EQUIPMENT MUST BE INSTALLED ABOVE AN INACCESSIBLE CEILING OR BEHIND A WALL. AN APPROPRIATE ACCESS DOOR SHALL BE PROVIDED AND THE LOCATION SHALL BE COORDINATED WITH THE ARCHITECT.
- 8. WHERE A CONFLICT OCCURS BETWEEN THE DOCUMENTS, IT SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT: CARRY AS PART OF THE BID THE LARGER QUANTITY AND OR MORE EXPENSIVE ITEM(S).
- 9. BEFORE INSTALLATION, COORDINATE THE WORK WITH OWNER-FURNISHED EQUIPMENT INCLUDING REQUIRED SERVICE CONNECTIONS, FACTORY START UPS, AND INSTALLATION OF FIELD DEVICES.
- 10. PROVIDE THE REQUIRED/SPECIFIED SLEEVES AND SEALS FOR PIPES OR CONDUIT PENETRATING INTERIOR AND EXTERIOR WALLS OR FLOOR SLABS.
- 11. INSTALL FLOOR-MOUNTED EQUIPMENT ON A CONCRETE HOUSEKEEPING PAD.
- 12. SEISMICALLY SUPPORT EQUIPMENT AS REQUIRED BY CODE, THE AUTHORITY HAVING JURISDICTION, AND/OR AS SPECIFIED. SUBMIT ENGINEERED INSTALLATION DETAILS PER THE SPECIFICATIONS. THE CONTRACTORS SEISMIC ENGINEER SHALL REVIEW THE INSTALLATION AND PROVIDE A REPORT ON THE FINDINGS
- 13. PROVIDE CONDUIT, AND ALL OTHER ACCESSORIES AS REQUIRED FOR PROPER AND PROFESSIONAL SYSTEMS INSTALLATION.
- 14. TEST AND BALANCE ALL ELECTRICAL SYSTEMS. PROVIDE ADDITIONAL TESTS AS REQUIRED BY THE SPECIFICATIONS.
- 15. DO NOT INSTALL PIPING OR DUCTWORK OVER ELECTRICAL PANELS, TRANSFORMERS, SPECIAL EQUIPMENT, ELEVATOR MACHINE ROOMS OR SHAFTS.
- 16. DO NOT INSTALL ANY SYSTEMS IN OR THROUGH ELEVATOR MACHINE ROOMS THAT DO NOT SERVE THE ROOM. MAINTAIN A MINIMUM OF SEVEN (7) FOOT HEAD CLEARANCE IN THE ELEVATOR MACHINE ROOM.
- 17. DO NOT INSTALL, IN STAIRWELLS OR STAIRWELL WALLS, PIPING, DUCTWORK, CONDUIT OR OTHER DEVICES OR EQUIPMENT NOT ASSOCIATED WITH OR SERVING THE RESPECTIVE STAIR.
- 18. PROVIDE PIPE EXPANSION COMPENSATION FOR THE VARIOUS PIPING SYSTEMS. SUBMIT ENGINEERED DETAILS FOR APPROVAL AND VERIFY INSTALLATION IS IN ACCORDANCE WITH CODE. THE CONTRACTOR'S CONSULTING ENGINEER SHALL REVIEW THE INSTALLATION AND PROVIDE A REPORT ON THE FINDINGS.
- 19. PROVIDE ADDITIONAL TRANSITIONS AND OFFSETS IN ALL CONDUIT FOR COORDINATION WITH BUILDING STRUCTURE AND CONSTRUCTION.
- 20. NO MECHANICAL OR ELECTRICAL SYSTEM COMPONENTS MAY BE SUPPORTED FROM STRUCTURAL BRACED

#### RENOVATION

- 1. THIS PROJECT INVOLVES THE RENOVATION OF AN EXISTING FACILITY; BEFORE SUBMITTING THE BID, CONTRACTORS SHALL VISIT THE SITE AND BECOME THOROUGHLY FAMILIAR WITH THE EXISTING CONDITIONS UNDER WHICH THE PROJECT IS TO BE COMPLETED.
- 2. CONTRACTORS SHALL BE HELD RESPONSIBLE FOR ASSUMPTIONS, OMISSIONS OR ERRORS MADE AS A RESULT OF FAILURE TO BECOME FULLY FAMILIAR WITH THE EXISTING CONDITIONS.
- 3. IT IS NOT THE INTENT OF THESE DOCUMENTS TO SHOW EVERY DEVICE, APPURTENANCE, WIRE OR CONDUIT TO BE REMOVED. MEP EQUIPMENT, UNITS, AND SYSTEMS NOT BEING REUSED, SHALL BE REMOVED IN THEIR ENTIRETY INCLUDING ASSOCIATED HANGERS, SUPPORTS, BASES, PADS, CONDUITS, WIRES, INSULATION, AND CONTROLS BACK TO THE POINT OF ORIGIN.
- 4. EQUIPMENT, OR CONDUIT SHALL NOT BE ABANDONED IN-PLACE UNLESS SPECIFICALLY SO NOTED.

STANDARDS; TURN OVER TO THE OWNER, EQUIPMENT SO INDICATED.

- 5. PROPERLY DISPOSE OF DEMOLISHED EQUIPMENT IN COMPLIANCE WITH CODES, REGULATIONS, AND DEP
- 6. RELOCATE EXISTING EQUIPMENT, DEVICES, PIPING, WIRING, AND RELATED SYSTEMS AS REQUIRED FOR CONSTRUCTION PURPOSES. ALL EXISTING SYSTEMS SHALL BE FULLY OPERATIONAL, INCLUDING RECONNECTION TO SERVICES AND UPGRADED SYSTEMS. ALL RELOCATED EQUIPMENT SHALL BE PROTECTED DURING CONSTRUCTION.
- 7. PROVIDE TEMPORARY CONNECTIONS AND SYSTEM MODIFICATIONS AS REQUIRED FOR CONSTRUCTION AND PHASING PURPOSES.
- 8. INCLUDE ALL WORK REQUIRED TO ALLOW PHASED CONSTRUCTION WHEN NECESSARY. COORDINATE WITH GENERAL CONTRACTOR/CONSTRUCTION MANAGER FOR PHASING REQUIREMENTS.
- 9. ALL EXISTING EQUIPMENT, FIXTURES, AND DEVICES TO BE REMOVED AND RELOCATED SHALL BE FIELD VERIFIED FOR EXACT QUANTITY AND CONDITION; KEEP AN ACCURATE RECORD OF STORED EQUIPMENT AND ITS
- 10. REBALANCE NEW AND EXISTING ELECTRICAL SYSTEMS ASSOCIATED WITH THE RENOVATION, INCLUDING RENOVATED AREAS AND AREAS AFFECTED BY SYSTEM MODIFICATIONS.
- 11. SYSTEMS REQUIRING TO REMAIN IN OPERATION DURING DEMOLITION AND RENOVATION SHALL BE CAREFULLY PROTECTED FROM DAMAGE AND CONTAMINATION BY THE CONSTRUCTION PROCESS.

#### **ELECTRICAL**

- 1. IT IS NOT THE INTENTION TO SHOW EVERY FITTING, WIRE, OR DEVICE. ALL SUCH ITEMS SHALL BE FURNISHED AND INSTALLED AS NECESSARY FOR A COMPLETE SYSTEM.
- 2. CONCEAL RACEWAYS IN FINISHED AREAS. RACEWAYS WITHIN MECHANICAL AND ELECTRICAL ROOMS MAY BE SURFACE-MOUNTED.
- 3. DO NOT INSTALL CONDUIT IN CONCRETE SLABS, UNLESS SPECIFICALLY APPROVED BY THE STRUCTURAL
- 4. BOND ALL OF THE FOLLOWING SERVICES TOGETHER PER THE NEC: POWER, TELECOMMUNICATIONS, CATV AND LIGHTNING PROTECTION.

#### 5. PROVIDE GROUND FAULT WEATHER PROOF RECEPTACLES AT ALL EXTERIOR LOCATIONS.

#### PANELBOARD SCHEDULE

#### **GENERAL NOTES:**

- 1. SEE SPECIFICATION SECTION "PANELBOARDS" FOR FEATURES OF PANELBOARDS.
- 2. VERIFY SIZE, QUANTITY AND TYPES OF CIRCUIT BREAKERS IN PANELBOARDS WITH PLANS, RISERS, SCHEDULES AND SPECIFICATION.
- 3. ALL PANELBOARDS ARE LIGHTING AND APPLIANCE BRANCH CIRCUIT PANELBOARDS UNLESS LISTED OTHERWISE.

PANELBOARD DESIGNATION	VOLTAGE	MAIN BUS SIZE	MAIN OCPD SIZE	MOUNTING	POLE CAPACITY	MIN. AISC RATING	NOTES	CIRCUITS					
								AMPS	POLES	BRANCH	FEEDER	SPARE	NOTES
.P3	208Y/120	225A	100A	SURFACE	42	22,000		20	2	6	_	2	Α
								20	1	3	_	23	
								_	1	_	_	-	

A. PROVIDE 30 MA GROUND FAULT CIRCUIT INTERRUPTER CIRCUIT BREAKERS.

#### **LUMINAIRE SCHEDULE**

#### NOTES:

LIGHT LOSS FACTOR: 0.85 OVERALL


- . BIDS SHALL BE BASED ON THE LUMINAIRE SCHEDULE BELOW AND THE SPECIFICATIONS. REFER TO THE ELECTRICAL SPECIFICATIONS FOR ADDITIONAL GENERAL REQUIREMENTS.
- 2. PROVIDE MOCK UP WITH (1) EA1A, (2) EA1B, (3) EA2A, (1) EA2B AND (1) EA2C FOR NORTH AND EAST SIDES BEFORE ORDERING LUMINAIRES.
- 3. AS PART OF OF SHOP DRAWING SUBMITTAL, EQUIVALENT MANUFACTURER SHALL PROVIDE POINT BY POINT VERTICAL FOOT CANDLE CALCULATION WITH RENDERING ALONG CUPOLA. PROVIDE AVERAGE, MINIMUM, MAXIMUM, AND UNIFORMITY OF FOOT CANDLE LEVEL AS PART OF CALCULATION. FOOT CANDLE CALCULATION CRITERIA ARE AS FOLLOWS: AVERAGE FOOT CANDLE: 6.5 OR BETTER, MINIMUM FOOT CANDLE: 4.5 TO 5.0 OR BETTER, MAXIMUM FOOT CANDLE: 8.5 OR BETTER, UNIFORMITY: BETTER THAN 2.1 MAXIMUM-TO-MINIMUM, CALCULATION POINT SPACING 2FT ON CENTER.

TYPE	MANUFACTURER	FIXTURE DESCRIPTION	VOLTS	LAMPS
A1A	COLOR KINETICS eW BLAST POWERCORE #523-000069-13/ 120-000019-04 SERIES OR ACCEPTABLE EQUIVALENT	POST MOUNTED WHITE LED LUMINAIRE: DIE—CAST ALUMINUM HOUSING; BLACK FINISH; 36° BEAM ANGLE OPTICS, FROSTED TEMPERED FLAT GLASS LENS; INTEGRAL MOUNTED LED DRIVER; EACH LED HAS A CLEAR CONICAL PLASTIC REFLECTOR WITH RECESSED MICRO—PRISMATIC BOTTOM CENTER; EACH REFLECTOR IS ENCASED IN A MOLDED BLACK PLASTIC FRAME; VERTICAL BASE—UP POSITION; PROVIDE WITH 6 FEET UNIFIED POWER/DATA CABLE; FIXTURE SHALL HAVE A LOCKING CANOPY BASE FOR 350° ROTATION AND 110° FIXTURE TILTING; POWER FACTOR CORRECTION OF AT LEAST 0.85; LUMENS MAINTENANCE: 70,000 HOURS L70 @25°C; MEET IP66 REQUIREMENT; UL LISTED FOR WET LOCATION; COMPLY WITH RANDOM VIBRATION MIL—STD 810 CATEGORY 24; PASS TEMPERATURE RANGE OPERATIONAL TESTING FROM —40°C TO 50°C.; BLACK FINISH BARN DOORS; PROVIDE MOUNTING BRACKET, HARDWARE AND ALL ACCESSORIES FOR COMPLETE INSTALLATION; SEE ARCHITECTURAL PLANS FOR MOUNTING DETAILS.	120 V	50W TOTAL 2141 LUMENS 82 CRI 4000K
EA1B	COLOR KINETICS eW BLAST POWERCORE #523-000069-11/ 120-000019-04 SERIES OR ACCEPTABLE EQUIVALENT	LUMINAIRE AND LAMP SAME AS [EA1A] EXCEPT WITH 21° BEAM ANGLE OPTICS, FROSTED TEMPERED FLAT GLASS LENS.	120 V	50W TOTAL 2141 LUMENS 82 CRI 4000K
A2A	COLOR KINETICS eW REACH POWERCORE #523-000044-01/ 120-000068-01/4725.BD SERIES OR ACCEPTABLE EQUIVALENT	POST MOUNTED WHITE LED LUMINAIRE: DIE—CAST ALUMINUM HOUSING; BLACK FINISH; 23° BEAM ANGLE OPTICS, CLEAR TEMPERED FLAT GLASS ENCLOSURE WITH FROSTED PLASTIC OUTER LENS; SPREAD LENSES; INTEGRAL MOUNTED LED DRIVER; PROVIDE WITH 6 FEET LEADER CABLE; MOLDED PLASTIC REFLECTORS; FIXTURE SHALL HAVE A MOUNTING BRACKET THAT ALLOWS SIMPLE POSITIONING AND 360° ROTATION; POWER FACTOR CORRECTION OF AT LEAST 0.95; LUMENS MAINTENANCE: 70,000 HOURS L70 @25°C; MEET IP66 REQUIREMENT; UL LISTED FOR WET LOCATION; COMPLY WITH RANDOM VIBRATION MIL—STD 810 CATEGORY 24; PASS TEMPERATURE RANGE OPERATIONAL TESTING FROM —40°C TO 50°C.; BLACK FINISH BARN DOORS; PROVIDE MOUNTING BRACKET, YOKE, HARDWARE AND ALL ACCESSORIES FOR COMPLETE INSTALLATION; SEE ARCHITECTURAL PLANS FOR MOUNTING DETAILS.	120 V	250W TOTAL 9935 LUMENS 80 CRI 4000K
A2B	COLOR KINETICS eW REACH POWERCORE #523-000044-01/ 120-000068-01/02/ 4725.BD SERIES OR ACCEPTABLE EQUIVALENT	LUMINAIRE AND LAMP SAME AS [EA2A] EXCEPT WITH 23° BEAM ANGLE OPTICS, FROSTED TEMPERED FLAT GLASS LENS ON HALVES OF THE LUMINAIRE AND 40° BEAM ANGLE OPTICS, FROSTED TEMPERED FLAT GLASS LENS ON OTHER HALVES OF THE LUMINAIRE.	120 V	250W TOTAL 9935 LUMENS 80 CRI 4000K
EA2C	COLOR KINETICS eW REACH POWERCORE #523-000044-01/ 120-000068-02/03/ 4725.BD SERIES OR ACCEPTABLE EQUIVALENT	LUMINAIRE AND LAMP SAME AS [EA2A] EXCEPT WITH 40° BEAM ANGLE OPTICS, FROSTED TEMPERED FLAT GLASS LENS ON HALVES OF THE LUMINAIRE AND 63° BEAM ANGLE OPTICS, FROSTED TEMPERED FLAT GLASS LENS ON OTHER HALVES OF THE LUMINAIRE.	120 V	250W TOTAL 9935 LUMENS 80 CRI 4000K

ABBREVIATIONS  STATE OF CONNECTICUT OFFICE OF LEGISLATIVE MANAGEMENT	- -				
REVISION	OTTICE OF BEGIGERITIVE MANAGEMENT				
mark date description PLANS PREPARED BY  D) (1.1. IN ITEM CERT) (1CFC) date  04/13	e /13/12				
BVH INTEGRATED SERVICES scale NON					
project drawn CONNECTICUT'S OLD STATE HOUSE MB	-				
ROOF REPLACEMENT & FACADE RENOVATIONS   appro   800 MAIN STREET   IP   HARTFORD, CT 06106	roved				
drawin	wing no.				
10-11-006 CAD no. Project no. CT-7301 E	E-001				


### **DEMOLITION NOTES**

- REMOVE EXISTING ROOF MOUNTED HID METAL HALIDE LAMP LIGHTING FIXTURE. REMOVE EXISTING CONDUIT AND WIRING BACK TO THE SOURCES.
- 2 EXISTING VERTICAL DOWNSPOUT GUTTER TO BE REMOVED BY OTHERS.
- 3 EXISTING HORIZONTAL MOUNTED ROOF GUTTER TO REMAIN.



#### **GENERAL NOTES**

- EXISTING DE-ICING HEAT TRACING CABLING SYSTEM EQUIPMENTS FOR ROOF GUTTERS SHALL BE REMOVED BY THE OWNER UPTO POWER CONNECTION. ELECTRICAL CONTRACTOR SHALL DISCONNECT AND REMOVE EXISTING POWER CONNECTION, ASSOCIATED BACKBOXES, CONDUITS AND WIRING BACK TO THE SOURCES.
- 2. REMOVE ALL EXISTING CONVENIENCE POWER OUTLETS MOUNTED ON ROOF, INCLUDING WITH ALL ASSOCIATED EXISTING CONDUITS AND WIRING BACK TO THE SOURCES.



#### **DRAWING NOTES**

- 1 PROVIDE WEATHER-PROOF GF DUPLEX RECEPTACLE OUTLET IN THERMOPLASTIC NEMA 4 ENCLOSURE. PROVIDE DOUBLE GANG BACK BOXES.
- PROVIDE WEATHERPROOF JUNCTION BOX FOR POWER WIRING FOR DE-ICING HEAT TRACING SYSTEM FOR ROOF GUTTERS. JUNCTION BOX SHALL BE MOUNTED ON THE POST. COORDINATE EXACT LOCATION IN THE FIELD. CONDUIT SHALL RISE UP IN THE POST FROM ATTIC.
- 3 EXTERIOR ROOF MOUNTED LIGHTING FIXTURES CIRCUIT SHALL BE CONTROLLED THRU TIME CLOCK AND CONTACTOR. SEE EXTERIOR ROOF MOUNTED LIGHTING CONTROL WIRING DETAIL ON DRAWING # E-101 FOR MORE INFORMATION. PROVIDE 2 #10 & 1 #10 GND IN 1"C. REUSE EXISTING SPARE 20A-1P C/B LOCATED IN EXISTING POWER PANEL "LP2" LOCATED IN ATTIC TO FEED NEW CIRCUIT.
- 4 PROVIDE 2 #10 & 1 #10 GND IN 1"C.
- 5 PROVIDE 20A-2P, 30MA GROUND FAULT TYPE C/B IN NEW POWER PANEL "LP3" LOCATED IN ATTIC. PROVIDE 2 #10 & 1 #10 GND IN 1"C.

#### **GENERAL NOTES**

- DE-ICING HEAT TRACING SYSTEM EQUIPMENTS FOR ROOF GUTTERS SHALL BE FURNISHED AND INSTALLED BY THE OWNER.
- NEW SENSOR FOR DE—ICING HEAT TRACING SYSTEM SHALL BE INSTALLED IN ROOF GUTTER. COORDINATE EXACT LOCATION IN THE FIELD.
- 3. NO EXPOSED CONDUITS SHALL BE RUN ON THE ROOF. ALL CONDUITS SERVING ELECTRICAL EQUIPMENT OR DEVICES LOCATED ON THE ROOF SHALL RISE UP DIRECTLY FROM ATTIC TO THE LOCATION OF EQUIPMENT OR DEVICES THRU POST STRUCTURAL TUBES.
- 4. PROVIDE POST MOUNTED WEATHER—PROOF JUNCTION BOXES FOR POWER WIRING FOR ALL LIGHTING FIXTURES. ALL CONDUITS SERVING LIGHTING FIXTURES ON ROOF SHALL BE RUN IN THE POST STRUCTURAL TUBES.

STATE OF CONNECTICUT
OFFICE OF LEGISLATIVE MANAGEMENT

REVISION

mark date description

PLANS PREPARED BY
BVH INTEGRATED SERVICES
SO GRIFFIN ROAD SOUTH, BLOOMFIELD, CT 06002


project
CONNECTICUT'S OLD STATE HOUSE
ROOF REPLACEMENT & FACADE RENOVATIONS
800 MAIN STREET
HARTFORD, CT 06106


CAD no.

CAD no.

E-101


10-11-006






PROPOSED NEW CONDUITS RISER
UP IN THE CHASE ABOVE THE
FLOOR FOR POWER WIRING TO FEED NEW POWER PANEL "LP3" LOCATED IN ATTIC. COORDINATE EXACT ROUTING WITH OTHER EXISTING UTILITIES. Holcombe Center Old State House Entry Floor Scale 1/16" = 1'-0"

> **ENTRY LEVEL PLAN** SCALE: 1/16"=1'-0"



SCALE: 1/16"=1'-0"

**SECOND FLOOR PLAN** 



THIRD FLOOR PLAN SCALE: 1/16"=1'-0"

drawing title
ELECTRICAL PART PLANS STATE OF CONNECTICUT OFFICE OF LEGISLATIVE MANAGEMENT REVISION PLANS PREPARED BY mark date description BVH INTEGRATED SERVICES | 04/13/12 | scale 50 GRIFFIN ROAD SOUTH, BLOOMFIELD, CT 06002 1/16"=1'-0" project drawn by

CONNECTICUT'S OLD STATE HOUSE MB

ROOF REPLACEMENT & FACADE RENOVATIONS approved 800 MAIN STREET HARTFORD, CT 06106 drawing no. E-201 project no. CT-7301

10-11-006